



**Job wise labour rates for maintenance works for the year 2019-20 - justification thereof.**

S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3 Straightening of leaned poles:-	4	5	6	7	8	9	10	11	12
1	(a) Straightening of 140 Kg 8 mtr long PCC poles (Including pit digging, Straightening & back filling with boulders & ramming including cost of boulders)	335	333	3	2	35.50	250	285	57	342
	(b) Straightening of 272 Kg 9.1 mtr long PCC poles (Including pit digging, Straightening & back filling with boulders & ramming including cost of boulders)	486	333	4	2	80	333	413	83	496
	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) (Including pit digging, Straightening & back filling with boulders & ramming including cost of boulders)	605	333	5	2	97.50	416	514	103	617
	(d) R.S.Joist (125x70 mm) (Including pit digging, Straightening & back filling with boulders & ramming including cost of boulders)	503	333	4	2	94.50	333	428	86	513
2	Dismantling of damaged old support completely (For 33 KV & 11 KV lines)									
	(a) 140 Kg 8 mtr long PCC pole Taking out of V cross arm, top clamp insulators, 4 pin cross arm etc. de-erection of pole & shifting	279	333	2	2	70	167	237	47	284
	(b) 272 Kg 9.1 Mtr long PCC Pole Taking out of V cross arm, top clamp insulators etc., de-erection of pole & shifting	304	333	2	2	90.50	167	257	51	308
	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) Cutting of pole by gas cutter / Dismantling, taking out of V-cross arm, top clamp insulators etc. shifting & loading in Board's vehicle.	853	333	5	2	304.50	416	721	144	865
3	(d) R.S.Joist (125x70 mm) Cutting of pole by gas cutter / Dismantling, taking out of cross arm, 4 pin cross arm and insulators etc. shifting and loading in company's Vehicle	756	333	4	2	305	333	638	128	766
	Renovation of stay providing stay wire only where stay rod is found intact	151	333	2	1.50	4	125	129	26	155

  
 (A.K. Lakhera-90440560)  
 Superintending Engineer  
 City Circle-I, CSPDCL, Raipur

S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	New stay- Pit digging, grouting, concreting & erection									
4	(i) New stay for 33 KV line 20 mm	493	358	4	2	60.50	358	419	84	502
	(ii) New stay for 11 KV line 16 mm	232	358	1	2	105.50	90	195	39	234
(a)	For urban areas with concreting cement will be provided by the board	243	388	1	2	107.50	97	205	41	245
(b)	For rural areas with stone block	212	388	1	2	81.50	97	179	36	214
	Painting of poles : cleaning of metallic surface by wire brush, 2 coats of red oxide & 1 coat of Aluminium paint on all the steel surfaces, paint will be provided by the board & wire brush will be provided by the contractor.									
5	(a) Rail pole, R.S.Joist, H-Beam	237	388	1	2	102.50	97	200	40	239
	(b) V-cross arm & Top clamp 11 KV & 33 KV	175	388	2	1.50	3.50	146	149	30	179
	(c) LT 3 / 4 / 5 Pin cross arm each	65	388	1	1	6.50	49	55	11	66
	(d) DC channel (8',5',4', SPC) for 33 KV & 11 KV	133	388	2	1	16	97	113	23	136
6	(a) Numbering of poles:- Preparing base by black paint at the height of 05 feet from ground level for writing pole number with white paint of size 4" including cost of paint and labour charges.	62	388	1	1	4.50	49	53	11	64
	(b) Obtaining G.I.S. co-ordinates per pole (latitude & longitude) for works to be executed in R-APDRP town areas.	5.00 per location/pole					5.00 per location/pole	5.00 per location/pole		5.00 per location/pole
	Painting of X-mer:- Cleaning of X-mer body with water, brush, detergent & providing paint labour charges only, paint shall be provided by board									
7	(a) 25 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	302	358	2	2	76.50	179	256	51	307
	(b) 50/63 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	364	358	2	2	128	179	307	61	368
	(c) 100 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	426	358	2	2	180	179	359	72	431
	(d) 200 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	439	358	2	2	190.50	179	370	74	443
	(e) 315 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	463	358	2	2	211	179	390	78	468
	(f) 500 KVA X-mer 2 coats of Red oxide & one coat of Gray paint	587	358	2	2	314	179	493	99	592

  
 (A.K. Lakhera-90440560)  
 Superintending Engineer  
 City Circle-I, CSPDCL, Raipur



S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Wing Hour/ per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019- 20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Straitening of tilted V cross arm & top clamps provided with back clamps									
	33 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	132	358	2	1.25	0.50	112	112	22	135
8	11 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	55	358	1	1	2	45	47	9	56
	33 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	34	358	1	0.65	0	29	29	6	35
	11 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	34	358	1	0.65	0	29	29	6	35
9	Replacement of bent V cross arm :- Taking out of bent cross arm & replacement by new one along with taking out of 02 No. insulators, binding opening & again providing the same.									
	33 KV	146	333	1	2	40.50	83	124	25	149
	11 KV	105	333	1	1	47	42	89	18	107
10	Replacement of Top clamps:- Taking out of damaged top clamp, 01 No. insulator opening, binding & again providing New top clamp along with fixing of insulator & rewinding									
	33 KV	80	333	1	1.65	0	69	69	14	82
	11 KV	39	333	1	0.77	1	32	33	7	40
11	Renovation of earthing of poles for single locations (material shall be supplied by the Board)									
	33 KV	142	333	1	1	77.50	42	119	24	143
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
	11 KV	136	333	1	1	72.50	42	114	23	137
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
	LT line	99	333	1	1	42	42	84	17	100
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
12	Making holes on Rails, R.S.Joist, H-Beam by gas kit / Ratchet for earthing / Top clamp fixing etc.	75	333	1	1	22	42	64	13	76
13	Replacement of Damaged Disc insulator taking out of line conductor, replacement of Disc & again fixing the line conductor & renovation of jumper using trifer or turn buckle.	281	333	2	2	71.50	167	238	48	286

S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Replacement of Damaged Pin insulator									
14	(a) 33 KV	50	333	1	1	1	42	43	9	51
	(b) 11 KV	31	333	1	0.63	0	26	26	5	31
	Restringing of line conductor for 33/11 KV line work includes opening of binding of conductors from the insulators taking out of conductors from the Disc & refensioning the conductor & rewinding of it as the insulator (ACSR / AAAC Conductor) rates are taken per Km per phase									
15	(a) Raccoon & Dog conductor per Km / conductor	1362	333	7	3	282	874	1156	231	1387
	(b) Rabbit conductor	955	333	6	2	308.50	500	808	162	970
	(c) Weasel	761	333	4	2	309	333	642	128	770
	(d) Squirrel	566	333	4	1	309	167	476	95	571
16	Replacement / AUGUMENTATION of line conductor (for 33/11 KV) The work includes opening the binding of insulators of the sections, dismantling old conductors & coiling the conductor properly. laying out New conductor & tensioning it on the line with proper sag & binding of the conductor with insulator (ACSR & AAC) 1.5 times of standard rate.									
	(a) Raccoon & Dog conductor per Km / conductor	3962	333	10	7	458	2914	3372	674	4046
	(b) Rabbit conductor	3166	333	10	6	200.50	2498	2698	540	3238
	(c) Weasel	2441	333	10	4	409	1665	2074	415	2489
	(d) Squirrel	2255	333	10	4	254	1665	1919	384	2303
	Replacement of fixed & moving contacts of AB awitch with (Adjustment of complete unit greasing and renovation of jumper wire each location)									
17	(a) 33 KV	319	333	2	2	103	167	270	54	323
	(b) 11 KV	206	333	2	2	9	167	176	35	211
18	Providing stay insulator to LT lines, cutting of stay wire binding of stay insulators & erection & tightening of stay	114	333	1	2	14	83	97	19	117



S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019- 20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
19	a. Re-stringing of line conductor in LT, removing of service lines, diamond guarding and binding, retensioning of the conductor and re-providing diamond guarding, service jumpering etc. (considering 08 services per span)	341	333	2	2	121.50	167	288	58	346
	b. Re-stringing of line conductor in LT, diamond guarding and binding, retensioning of the conductor and re-providing diamond guarding, service jumpering etc. (considering 08 services per span)	262	333	2	2	55.50	167	222	44	266
	Providing extension piece to maintain safe clearance as per IE rules (each location)									
20	a. 33 KV each location	343	333	2	2	123	167	290	58	347
	b. 11 KV each location	269	333	2	2	61.50	167	228	46	274
	Straitening of DP	319	333	2	2	103.50	167	270	54	324
	Pit digging 50%, loosening of stay straightening of DP tightening of stay and back filling of pit									
21	a. 33 KV									
	1 272 Kg PCC pole	817	333	4	2	355.50	333	689	138	826
	2 Rail / H-Beam / R.S.Joist	1053	333	5	3	268.50	624	893	179	1071
	b. 11 KV									
	1 140 Kg PCC pole	592	333	4	2	168	333	501	100	601
	2 Rail / H-Beam / R.S.Joist	761	333	4	2	309	333	642	128	770
	Renovation of Carpet guarding									
22	a. 33 KV	1550	333	8	3	316.50	999	1316	263	1579
	b. 11 KV	852	333	5	2	304	416	720	144	864
	c. LT line	352	333	2	2	131	167	298	60	357
	Service line renovation (only labour charges)									
23	a. Single phase	156	333	2	1.60	0	133	133	27	160
	b. Three phase	263	333	2	2	56.50	167	223	45	268
24	LT jumper renovation	32	333	1	0.65	0	27	27	5	32

(A.K. Lakhra-90440560)  
Superintending Engineer  
City Circle-I, CSPDCL, Raipur

S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Tree cutting and trimming of tree branches :-									
25	a. LT line	93	358	1	1.77	0	79	79	16	95
	b. 11 KV Line	105	358	1	2	0	90	90	18	107
	c. 33 KV Line	178	358	2	1.50	17	134	151	30	182
	Replacement of Distribution box	401	358	2	2	159	179	338	68	406
	Replacement of cable (3.5 core) Replacement will be with lugs materials will be provided by the Company									
26	a. 300 sq. mm.	617	358	4	2	164	358	522	104	626
	b. 150 sq. mm.	554	358	4	2	112	358	470	94	564
	c. 70 sq. mm.	423	358	3	2	90	269	359	72	430
	Replacement of DO fuse unit (each)									
27	a. 33 KV	169	333	2	1.50	19	125	144	29	173
	b. 11 KV	112	333	2	1	12	83	95	19	114
28	Replacement of phase main switch	226	333	2	2	25.50	167	192	38	230
29	Replacement of porcelain kit-kat	73	333	1	1.50	0	62	62	12	75
	Replacement of lightning arrester as per schedule									
30	a. 33 KV	131	333	1	2	28	83	111	22	134
	b. 11 KV	62	333	1	1.27	0	53	53	11	63
31	Replacement of Silica Jel	33	333	1	0.68	0	28	28	6	34
32	Renovations of Jumpers of DT S/s. alongwith lugging (material will be supply by the Company)	299	333	2	2	87	167	254	51	304
33	Commissioning of meter at DT (installation of meter box, meter, cabling, commissioning complete by skilled labour)	858	333	5	2	309	416	725	145	870




S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
<b>proposed Additional Job work already incorporated in 2018-19</b>										
1	Shifting of location of meter from inside to outside consumer premises labour charges									
a	Single phase connection	232	333	2	2	31	167	198	40	237
b	Three phase connection	366	333	3	2	61	250	311	62	373
2	Replacement of old meter box by installation of new pillar Box in complex including fixing & laying of cables and shifting of connection only labour charges	4667	333	10	8	639	3330	3969	794	4763
3	Indexing of consumer premises, survey, meter card fixing, writing of S/C no., line diagram preparation, from DT to consumer premises each DT wise	36	333	1	0.74	0	31	31	6	37
4	DT meter installation including CT / meter box and meter installation (only labour charges)	792	333	4	2	335	333	668	134	802
5	Laying of HT ABC cable (labour charges) 33 kV	8811	333	15	12	30	7493	7523	1505	9027
6	Laying of HT ABC cable (labour charges) 11 kV	6062	333	15	8	177	4995	5172	1034	6206
7	Fixing of LT junction box on the pole for providing LT connection	195	333	2	2	0	167	167	33	200
8	Providing Earthing of Distribution S/s including pit digging laying and connecting wire to support, X-mer etc. Back filling of pit by Black Cotton soil (only labour charges) per pitwise	792	333	4	2	335	333	668	134	802
<b>proposed Additional Job work already incorporated in proposal 2018-19</b>										
1	Cleaning of 33/11 KV S/s. Yard (approx. 75% area of S/s.) including removal of grasses, tree plants removal dusting etc.	3958.00	333	12	6	373	2997	3370	674	4044
2	Renovation of yard levelling and metalling with cleaning, scraning labour charges	2472.00	333	8	6	110	1998	2108	422	2530
	ABC cable end joint replacement and fixing		333							
a	Per phase	817	333	4	2	355.50	333	689	138	826
b	Straight joint	1325	333	6	4	129	999	1128	226	1354
c	LT end joint per phase	104	333	1	2	5	83	88	18	106
d	LT straight joint per phase	137	333	1	2	32.50	83	116	23	139

(A.K.-Lakhara-90440560)

Superintending Engineer  
City Circle-I, CSPDCL, Raipur

S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
4	UG XLPE Cable end joint replacement and fixing									
	a HT end joint per phase	1745	333	7	5	32	1457	1489	298	1787
	b Straight joint per phase	2150	333	7	6	85	1748	1833	367	2200
	X-mer maintenance work									
	i Replacement of stud ( HT/LT) labour charges only material provided by CSPDCL									
	a 63 KVA 11/0.4 KV X-mer	245	333	2	2	42	167	209	42	250
	b 100 KVA 11/0.4 KV X-mer	306.00	333	3	2	11	250	261	52	313
	c 200 KVA 11/0.4 KV X-mer	331.00	333	3	2	32	250	282	56	338
	d 315 KVA 11/0.4 KV X-mer	356	333	3	2	53	250	303	61	363
	e 500 KVA 11/0.4 KV X-mer	381.00	333	3	2	74	250	324	65	389
5	Job work for renovation of complete Maintenance of D X-mer with replacement of Oil seal, burnt stud HT & LT, filtration of X-mer Oil, opening and tightening of core and winding and painting including minor repairing such as replacement of burnt stud change of L.T/HT bushing etc.									
	a 63 KVA 11/0.4 KV X-mer	3850.00	333	6	8	1258	1998	3256	651	3907
	b 100 KVA 11/0.4 KV X-mer	4633.00	333	8	8	1260.50	2664	3925	785	4709
	c. 200 KVA 11/0.4 KV X-mer	5774.00	333	8	9	1887	2997	4884	977	5861
	d 315 KVA 11/0.4 KV X-mer	6916.00	333	8	10	2513.50	3330	5844	1169	7012
	e 500 KVA 11/0.4 KV X-mer	8200	333	8	12	2933	3996	6929	1386	8315
	Distribution box door repairing / providing new door and its replacement against damaged / missing (labour charges with material)									
6	A. Upto 100 KVA Distribution box	1520	388							1520
	B. Above 100 to 200 KVA Distribution box	1646	388							1646
	C. 300 to 500 KVA Distribution box	1774	388							1774
7	Providing BPL Connection with Material including labour charges (Meter board 10"x12" 01 no. GI Wire 16 swg, Earthing terminal 01 no. 1/2"-04 no. nuts and bolts with washer for fixing of board, Piano switch 5 Amp., 01 no. bulb Holder, 16 Amp. cut-out, 02 no. Screw for fixing in meter and cut-out etc., 1.5 mm. up to maximum 30 meter.) (Remark :- The cost service wire to deducted @ Rs. 5.00 per meter on the basis of actual length of wire reduced by 30 meter length).	411	388							411


  
 A.K. Lakshmi  
 Superintending Engineer  
 City Circle-1, CSPDCL, Raipur



S. No.	Particulars	Rate as per SOR for 2018-19	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2019-20 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
<b>proposed Additional essential work already incorporated in SOR 2018-19</b>										
1	Replacement of XLPE cable U/G and removing of faulty cable per span i.e. 100 mtr. Span (per span)	10863								10863
2	Replacement of AB cable and removing of faulty cable per span i.e. 100 mtr. Span (per span)	604								604
3	Replacement of XLPE U/G cable end terminal kit (per phase)	2414								2414
4	Replacement of straight joint for XLPE U/G cable (per phase)	3621								3621
5	a	1207								1207
	b	604								604
6	a	1811								1811
	b	604								604
<b>The labour engaged should be Minimum qualification at least 12 th passed having knowledge / working of computer preferable ITI Passed</b>										

**Remark:- Revision of above proposal is on the basis of following points**

1	The above rate has been revised according to wages declared by Labour Commissioner under Minimum Wage Act-1948 w.e.f 01.10.2018 to 31-03-2019 for unskilled labour Rs.333.00 per day, semi skilled labour Rs. 358.00 per day and skilled labour Rs. 388.00 per day as per circular of Assistant Labour Commissioner Raipur District Raipur.
2	Labour contractor have to bear the responsibility of the All labour Rules applicable to him i.e. EPF deduction / payment of income tax / GST, workmen compensation etc.
3	Contractor have to deposit the addle. Money as provision in bank एवं अन्य सम्बन्धि कर्मकार (नियोजन एवं सेवा शर्तों को विनियम) अधिनियम 1996 की धारा 18(1) एवं 18(3) सह पठित नियम 251 के अनुसार असंगठित क्षेत्र के कर्मकारों के हित के लिए नियोजकों से निर्माण लागत का एक प्रतिशत की दर से उपकर संबल को देय होगा जो कर्मकारों के हित के लिए विभिन्न कल्याणकारी योजनाओं में राशि का उपयोग किया जाना है।



(A.K. Lakhera-9044056)  
Superintending Engineer  
City Circle-I, CSPDCL, Raipur

अनुसूची-“ख”


अनुसूचित नियोजन भाग-एक के 45 नियोजन

(दिनांक 01.04.2018 से 30.09.2018 तक)

(दिनांक 01.10.2018 से 31.03.2019 तक)

क्र.	श्रमिकों का वर्ग	जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महंगाई भत्ता		कुल वेतन रूपये में		जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महंगाई भत्ता		कुल वेतन रूपये में	
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन		प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन
1	अकुशल -	अ	8320.00	320.00	300.00	11.54	8620.00	331.54 (332)	अ	8320.00	320.00	340.00	13.08	8660.00	333.08 (333)
		ब	8060.00	310.00	300.00	11.54	8360.00	321.54 (322)	ब	8060.00	310.00	340.00	13.08	8400.00	323.08 (323)
		स	7800.00	300.00	300.00	11.54	8100.00	311.54 (312)	स	7800.00	300.00	340.00	13.08	8140.00	313.08 (313)
2	अर्द्धकुशल -	अ	8970.00	345.00	300.00	11.54	9270.00	356.54 (357)	अ	8970.00	345.00	340.00	13.08	9310.00	358.08 (358)
		ब	8710.00	335.00	300.00	11.54	9010.00	346.54 (347)	ब	8710.00	335.00	340.00	13.08	9050.00	348.08 (348)
		स	8450.00	325.00	300.00	11.54	8750.00	336.54 (337)	स	8450.00	325.00	340.00	13.08	8790.00	338.08 (338)
3	कुशल -	अ	9750.00	375.00	300.00	11.54	10050.00	386.54 (387)	अ	9750.00	375.00	340.00	13.08	10090.00	388.08 (388)
		ब	9490.00	365.00	300.00	11.54	9790.00	376.54 (377)	ब	9490.00	365.00	340.00	13.08	9830.00	378.08 (378)
		स	9230.00	355.00	300.00	11.54	9530.00	366.54 (367)	स	9230.00	355.00	340.00	13.08	9570.00	368.08 (368)
4	उच्च कुशल -	अ	10530.00	405.00	300.00	11.54	10830.00	416.54 (417)	अ	10530.00	405.00	340.00	13.08	10870.00	418.08 (418)
		ब	10270.00	395.00	300.00	11.54	10570.00	406.54 (407)	ब	10270.00	395.00	340.00	13.08	10610.00	408.08 (408)
		स	10010.00	385.00	300.00	11.54	10310.00	396.54 (397)	स	10010.00	385.00	340.00	13.08	10350.00	398.08 (398)

टीप : न्यूनतम वेतन अधिनियम, 1948 के अन्तर्गत 45 अनुसूचित नियोजनों की सूची परिशिष्ट-“अ” तथा इस संबंध में स्पष्टीकरण परिशिष्ट-“ब” में देखें।

  
(आरो शर्मा)

श्रमायुक्त एवं सक्षम प्राधिकारी  
न्यूनतम वेतन अधिनियम, 1948  
छत्तीसगढ़, रायपुर




**अनुसूची- 'ग'**

विभिन्न शासकीय विभागों में कार्यरत दैनिक वेतन भोगी श्रमिकों एवं कर्मचारियों के मासिक एवं दैनिक न्यूनतम वेतन तथा परिवर्तनशील महँगाई भत्ता।  
(दिनांक 01.04.2018 से 30.09.2018 तक)

न्यूनतम वेतन तथा परिवर्तनशील महँगाई भत्ता।  
(दिनांक 01.10.2018 से 31.03.2019 तक)

क्र.	श्रमिकों का वर्ग	जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महँगाई भत्ता		कुल वेतन रूपये में		जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महँगाई भत्ता		कुल वेतन रूपये में	
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन		प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन
1	अकुशल -	अ	8320.00	277.33	300.00	10.00	8620.00	287.33 (287)	अ	8320.00	277.33	340.00	11.33	8660.00	288.67 (289)
		ब	8060.00	268.67	300.00	10.00	8360.00	278.67 (279)	ब	8060.00	268.67	340.00	11.33	8400.00	280.00 (280)
		स	7800.00	260.00	300.00	10.00	8100.00	270.00 (270)	स	7800.00	260.00	340.00	11.33	8140.00	271.33 (271)
2	अर्द्धकुशल -	अ	8970.00	299.00	300.00	10.00	9270.00	309.00 (309)	अ	8970.00	299.00	340.00	11.33	9310.00	310.33 (310)
		ब	8710.00	290.33	300.00	10.00	9010.00	300.33 (300)	ब	8710.00	290.33	340.00	11.33	9050.00	301.67 (302)
		स	8450.00	281.67	300.00	10.00	8750.00	291.67 (292)	स	8450.00	281.67	340.00	11.33	8790.00	293.00 (293)
3	कुशल -	अ	9750.00	325.00	300.00	10.00	10050.00	335.00 (335)	अ	9750.00	325.00	340.00	11.33	10090.00	336.33 (336)
		ब	9490.00	316.33	300.00	10.00	9790.00	326.33 (326)	ब	9490.00	316.33	340.00	11.33	9830.00	327.67 (328)
		स	9230.00	307.67	300.00	10.00	9530.00	317.67 (318)	स	9230.00	307.67	340.00	11.33	9570.00	319.00 (319)
4	उच्च कुशल -	अ	10530.00	351.00	300.00	10.00	10830.00	361.00 (361)	अ	10530.00	351.00	340.00	11.33	10870.00	362.33 (362)
		ब	10270.00	342.33	300.00	10.00	10570.00	352.33 (352)	ब	10270.00	342.33	340.00	11.33	10610.00	353.67 (354)
		स	10010.00	333.67	300.00	10.00	10310.00	343.67 (344)	स	10010.00	333.67	340.00	11.33	10350.00	345.00 (345)

टीप : इस संबंध में स्पष्टीकरण परिशिष्ट-"ब" में देखें।

  
(आरो शर्मा)

श्रमायुक्त एवं सक्षम प्राधिकारी  
न्यूनतम वेतन अधिनियम, 1948  
छत्तीसगढ़, रायपुर