

Job wise labour rates for maintenance works for the year 2020-21- Justification thereof.

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020- 21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Straitening of leaned poles:-									
(a)	Straitening of 140 Kg 8 mtr long PCC poles (Including pit digging Straitening & back filling with boulders & ramming including cost of boulders)	342	341	3	2	35.50	256	291	58	350
(b)	Straitening of 272 Kg 9.1 mtr long PCC poles (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	496	341	4	2	80	341	421	84	505
(c)	Rail pole / H-Beam / R.S.Joist (175x85 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	617	341	5	2	97.50	426	524	105	629
(d)	R.S.Joist (125x70 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	513	341	4	2	94.50	341	436	87	523
	Dismantling of damaged old support completely (For 33 KV & 11 KV lines)									
(a)	140 Kg 8 mtr long PCC pole Taking out of V cross arm, top clamp insulators, 4 pin cross arm etc. de-erection of pole & shifting	284	341	2	2	70	171	241	48	289
(b)	272 Kg 9.1 Mtr long PCC Pole Taking out of V cross arm, top clamp insulators etc., de-erection of pole & shifting	308	341	2	2	90.50	171	261	52	313
(c)	Rail pole / H-Beam / R.S.Joist (175x85 mm) Cutting of pole by gas cutter / Dismantling, taking out of V-cross arm, top clamp insulators etc. shifting & loading in Board's vehicle.	865	341	5	2	304.50	426	731	146	877
(d)	R.S.Joist (125x70 mm) Cutting of pole by gas cutter / Dismantling, taking out of cross arm, 4 pin cross arm and insulators etc. shifting and loading in company's Vehicle	766	341	4	2	305	341	646	129	775
3	Renovation of stay providing stay wire only where stay rod is found intact	155	341	2	1.50	4	128	132	26	158


**Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Raipur**

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Worki Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	New stay- Pit digging, gROUTING, concreting & erection									
	(i) New stay for 33 KV line 20 mm	502	366	4	2	60.50	366	427	85	512
	(ii) New stay for 11 KV line 16 mm	234	366	1	2	105.50	92	197	39	236
4	For urban areas with concreting cement will be provided by the board	245	396	1	2	107.50	99	207	41	248
	For rural areas with stone block	214	396	1	2	81.50	99	181	36	217
	Painting of poles : cleaning of metallic surface by wire brush, 2 coats of red oxide & 1 coat of Aluminium paint on all the steel surfaces, paint will be provided by the board & wire brush will be provided by the contractor.									
5	(a) Rail pole, R.S.Joist, H-Beam	239	396	1	2	102.50	99	202	40	242
	(b) V-cross arm & Top clamp 11 KV & 33 KV	179	396	2	1.50	3.50	149	152	30	182
	(c) LT 3 / 4 / 5 Pin cross arm each	66	396	1	1	6.50	50	56	11	67
	(d) DC channel (8',5',4', SPC) for 33 KV & 11 KV	136	396	2	1	16	99	115	23	138
	Numbering of poles:- Preparing base by black paint at the height of 05 feet from ground level for writing pole number with white paint of size 4" including cost of paint and labour charges.	64	396	1	1	4.50	50	54	11	65
6	(a)	5.00 per location/pole					5.00 per location/pole	5.00 per location/pole		5.00 per location/pole
	(b) Obtaining G.I.S. co-ordinates per pole (latitude & longitude) for works to be executed in R-APDRP town areas.									
	Painting of X-mer:- Cleaning of X-mer body with water, brush, detergent & providing paint labour charges only, paint shall be provided by board									
7	(a) 25 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	307	366	2	2	76.50	183	260	52	311
	(b) 50/63 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	368	366	2	2	128	183	311	62	373
	(c) 100 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	431	366	2	2	180	183	363	73	436
	(d) 200 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	443	366	2	2	190.50	183	374	75	448
	(e) 315 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	468	366	2	2	211	183	394	79	473
	(f) 500 KVA X-mer 2 coats of Red oxide & one coat of Gray paint	592	366	2	2	314	183	497	99	596

Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Haipur

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Workin Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020- 21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Straitening of tilted V cross arm & top clamps provided with back clamps									
8	33 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	135	366	2	1.25	0.50	114	115	23	138
	11 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	56	366	1	1	2	46	48	10	57
	33 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	35	366	1	0.65	0	30	30	6	36
	11 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	35	366	1	0.65	0	30	30	6	36
9	Replacement of bent V cross arm :- Taking out of bent cross arm & replacement by new one along with taking out of 02 No. insulators, binding opening & again providing the same.									
	(a) 33 KV	149	341	1	2	40.50	85	126	25	151
	(b) 11 KV	107	341	1	1	47	43	89	18	107
10	Replacement of Top clamps:- Taking out of damaged top clamp, 01 No. insulator opening, binding & again providing New top clamp along with fixing of insulator & rewinding									
	(a) 33 KV	82	341	1	1.65	0	70	70	14	84
	(b) 11 KV	40	341	1	0.77	1	33	34	7	41
	Renovation of earthing of poles for single locations (material shall be supplied by the Board)									
	(a) 33 KV	143	341	1	1	77.50	43	120	24	144
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
11	(b) 11 KV	137	341	1	1	72.50	43	115	23	138
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
	(c) L.T line	100	341	1	1	42	43	85	17	102
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
12	Making holes on Rails, R.S.Joist, H-Beam by gas kit / Ratchet for earthing / Top clamp fixing etc.	76	341	1	1	22	43	65	13	78
13	Replacement of Damaged Disc insulator taking out of line conductor, replacement of Disc & again fixing the line conductor & renovation of jumper using trifer or turn buckle.	286	341	2	2	71.50	171	242	48	290

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Worki Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Replacement of Damaged Pin insulator									
14	(a) 33 KV	51	341	1	1	1	43	44	9	52
	(b) 11 KV	31	341	1	0.63	0	27	27	5	32
	Restringing of line conductor for 33/11 KV line work includes opening of binding of conductors from the insulators taking out of conductors from the Disc & retensioning the conductor & rewinding of it as the insulator (ACSR / AAAC Conductor) rates are taken per Km per phase									
15	(a) Raccoon & Dog conductor per Km / conductor	1387	341	7	3	282	895	1177	235	1413
	(b) Rabbit conductor	970	341	6	2	308.50	512	820	164	984
	(c) Weasel	770	341	4	2	309	341	650	130	780
	(d) Squirrel	571	341	4	1	309	171	480	96	575
16	Replacement / AUGMENTATION of line conductor (for 33/11 KV) The work includes opening the binding of insulators of the sections, dismantling old conductors & coiling the conductor properly. laying out New conductor & tensioning it on the line with proper sag & binding of the conductor with insulator (ACSR & AAC) 1.5 times of standard rate.									
	(a) Raccoon & Dog conductor per Km / conductor	4046	341	10	7	458	2984	3442	688	4130
	(b) Rabbit conductor	3238	341	10	6	200.50	2558	2758	552	3310
	(c) Weasel	2489	341	10	4	409	1705	2114	423	2537
	(d) Squirrel	2303	341	10	4	254	1705	1959	392	2351
	Replacement of fixed & moving contacts of AB awitch with (Adjustment of complete unit greasing and renovation of jumper wire each location)									
17	(a) 33 KV	323	341	2	2	103	171	274	55	328
	(b) 11 KV	211	341	2	2	9	171	180	36	215
18	Providing stay insulator to LT lines, cutting of stay wire binding of stay insulators & erection & tightening of stay	117	341	1	2	14	85	99	20	119



Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Hubli


S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Workin Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020- 21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
19	a. Re-stringing of line conductor in LT, removing of service lines, diamond guarding and binding, retensioning of the conductor and reproviding diamond guarding, service jumpering etc. (considering 08 services per span)	346	341	2	2	121.50	171	292	58	350
	b. Re-stringing of line conductor in LT, diamond guarding and binding, retensioning of the conductor and reproviding diamond guarding, service jumpering etc. (considering 08 services per span)	266	341	2	2	55.50	171	226	45	271
20	Providing extension piece to maintain safe clearance as per IE rules (each location)		341							
	a. 33 KV each location	347	341	2	2	123	171	294	59	352
	b. 11 KV each location	274	341	2	2	61.50	171	232	46	278
	Straitening of DP	324	341	2	2	103.50	171	274	55	329
21	Pit digging 50%, loosening of stay straightning of DP tightening of stay and back filling of pit									
	a. 33 KV									
	1 272 Kg PCC pole	826	341	4	2	355.50	341	697	139	836
	2 Rail / H-Beam / R.S.Joist	1071	341	5	3	268.50	639	908	182	1089
	b. 11 KV									
	1 140 Kg PCC pole	601	341	4	2	168	341	509	102	611
	2 Rail / H-Beam / R.S.Joist	770	341	4	2	309	341	650	130	780
	Renovation of Carpet guarding									
22	a. 33 KV	1579	341	8	3	316.50	1023	1340	268	1607
	b. 11 KV	864	341	5	2	304	426	730	146	876
	c. LT line	357	341	2	2	131	171	302	60	362
	Service line renovation (only labour charges)									
23	a. Single phase	160	341	2	1.60	0	136	136	27	164
	b. Three phase	268	341	2	2	56.50	171	227	45	272
24	LT jumper renovation	32	341	1	0.65	0	28	28	6	33

Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Raipur,

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Workin Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Tree cutting and trimming of tree branches :-									
25	a. LT line	95	366	1	1.77	0	81	81	16	97
	b. 11 KV Line	107	366	1	2	0	92	92	18	110
	c. 33 KV Line	182	366	2	1.50	17	137	154	31	185
	Replacement of Distribution box	406	366	2	2	159	183	342	68	410
	Replacement of cable (3.5 core) Replacement will be with lugs materials will be provided by the Company									
26	a. 300 sq. mm.	626	366	4	2	164	366	530	106	636
	b. 150 sq. mm.	564	366	4	2	112	366	478	96	574
	c. 70 sq. mm.	430	366	3	2	90	275	365	73	437
	Replacement of DO fuse unit (each)									
27	a. 33 KV	173	341	2	1.50	19	128	147	29	176
	b. 11 KV	114	341	2	1	12	85	97	19	117
28	Replacement of phase main switch	230	341	2	2	25.50	171	196	39	235
29	Replacement of porcelain kit-kat	75	341	1	1.50	0	64	64	13	77
	Replacement of lightning arrester as per schedule									
30	a. 33 KV	134	341	1	2	28	85	113	23	136
	b. 11 KV	63	341	1	1.27	0	54	54	11	65
31	Replacement of Silica Jel	34	341	1	0.68	0	29	29	6	35
32	Renovations of Jumpers of DT S/s. alongwith lugging (material will be supply by the Company)	304	341	2	2	87	171	258	52	309
33	Commissioning of meter at DT (installation of meter box, meter, cabling, commissioning complete by skilled labour)	870	341	5	2	309	426	735	147	882


Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Raipur

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Work Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
proposed Additional Job work already incorporated in 2019-20										
1	Shifting of location of meter from inside to outside consumer premises labour charges									
a	Single phase connection	237	341	2	2	31	171	202	40	242
b	Three phase connection	373	341	3	2	61	256	317	63	380
2.	Replacement of old meter box by installation of new pillar Box in complex including fixing & laying of cables and shifting of connection only labour charges	4763	341	10	8	639	3410	4049	810	4859
3	Indexing of consumer premises, survey, meter card fixing, writing of S/C no., line diagram preparation, from DT to consumer premises each DT wise	37	341	1	0.74	0	32	32	6	38
4	DT meter installation including CT / meter box and meter installation (only labour charges)	802	341	4	2	335	341	676	135	811
5	Laying of HT ABC cable (labour charges) 33 kV	9027	341	15	12	30	7673	7703	1541	9243
6	Laying of HT ABC cable (labour charges) 11 kV	6206	341	15	8	177	5115	5292	1058	6350
7	Fixing of LT junction box on the pole for providing LT connection	200	341	2	2	0	171	171	34	205
8	Providing Earthing of Distribution S/s including pit digging laying and connecting wire to support, X-mer etc. Back filling of pit by Black Cotton soil (only labour charges) per pitwise	802	341	4	2	335	341	676	135	811
proposed Additional Job work already incorporated in proposal 2019-20										
1	Cleaning of 33/11 KV S/s. Yard (approx. 75% area of S/s.) including removal of grasses, tree plants removal dusting etc.	4044.00	341	12	6	373	3069	3442	688	4130
2	Renovation of yard levelling and metalling with cleaning, scraning labour charges	2529.60	341	8	6	110	2046	2156	431	2587
	ABC cable end joint replacement and fixing		341							
a	Per phase	826	341	4	2	355.50	341	697	139	836
b	Straight joint	1354	341	6	4	129	1023	1152	230	1382
c.	LT end joint per phase	106	341	1	2	5	85	90	18	108
d	LT straight joint per phase	139	341	1	2	32.50	85	118	24	141
	UG XLPE Cable end joint replacement and fixing									


Superintending Engineer
 (City Circle-1) C.S.P.D.C.L., Raipur


S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Work Hour per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
4	a HT end joint per phase	1787	341	7	5	32	1492	1524	305	1829
	b Straight joint per phase	2200	341	7	6	85	1790	1875	375	2250
	X-mer maintenance work									
	i Replacement of stud (HT/LT) labour charges only material provided by CSPDCL									
	a 63 KVA 11/0.4 KV X-mer	250	341	2	2	42	171	213	43	255
	b 100 KVA 11/0.4 KV X-mer	312.90	341	3	2	11	256	267	53	320
	c 200 KVA 11/0.4 KV X-mer	338.10	341	3	2	32	256	288	58	345
	d 315 KVA 11/0.4 KV X-mer	363	341	3	2	53	256	309	62	371
	e 500 KVA 11/0.4 KV X-mer	388.50	341	3	2	74	256	330	66	396
5	ii Job work for renovation of complete Maintenance of D X-mer with replacement of Oil seal, burnt stud HT & LT, filtration of X-mer Oil, opening and tightening of core and winding and painting including minor repairing such as replacement of burnt stud change of LT/HT bushing etc.									
	a 63 KVA 11/0.4 KV X-mer	3907.20	341	6	8	1258	2046	3304	661	3965
	b 100 KVA 11/0.4 KV X-mer	4709.40	341	8	8	1260.50	2728	3989	798	4786
	c. 200 KVA 11/0.4 KV X-mer	5860.80	341	8	9	1887	3069	4956	991	5947
	d 315 KVA 11/0.4 KV X-mer	7012.20	341	8	10	2513.50	3410	5924	1185	7108
	e 500 KVA 11/0.4 KV X-mer	8315	341	8	12	2933	4092	7025	1405	8430
	Distribution box door repairing / providing new door and its replacement against damaged / missing (labour charges with material)									
6	A. Upto 100 KVA Distribution box	1520	396							1520
	B. Above 100 to 200 KVA Distribution box	1646	396							1646
	C. 300 to 500 KVA Distribution box	1774	396							1774

Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Raipur

S. No.	Particulars	Rate as per SOR for 2019-20	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2020-21 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
7	Providing BPL Connection with Material including labour charges (Meter board 10"x12" 01 no. GI Wire 16 swg, Earthing terminal 01 no. 1/2"-04 no. nuts and bolts with washer for fixing of board, Piano switch 5 Amp, 01 no. bulb Holder, 16 Amp. cut-out, 02 no. Screw for fixing in meter and cut-out etc., 1.5 mm. up to maximum 30 meter.) (Remark :- The cost service wire to deducted @ Rs. 5.00 per meter on the basis of actual length of wire reduced by 30 meter length).	411	396							411
proposed Additional essential work already incorporated in SOR 2019-20										
1	Replacement of XLPE cable U/G and removing of faulty cable per span i.e. 100 mtr. Span (per span)	10863								10863
2	Replacement of AB cable and removing of faulty cable per span i.e. 100 mtr. Span (per span)	604								604
3	Replacement of XLPE U/G cable end terminal kit (per phase)	2414								2414
4	Replacement of straight joint for XLPE U/G cable (per phase)	3621								3621
5	a Replacement of AB cable end joint per phase including material of good quality	1207								1207
	b Replacement of AB cable end joint per phase (only labour charges)	604								604
6	a Replacement of AB cable straight joint including material of good quality (per phase).	1811								1811
	b Replacement of AB cable straight joint (only labour charges)	604								604

Remark:- Revision of above proposal is on the basis of following points

1	The above rate has been revised according to wages declared by Labour Commissioner under Minimum Wage Act-1948 w.e.f 01.10.2019 to 31-03-2020 for unskilled labour Rs.341.00 per day, semi skilled labour Rs. 366.00 per day and skilled labour Rs. 396.00 per day as per circular of Assistant Labour Commissioner Raipur District Raipur.
2	Labour contractor have to bear the responsibility of the All labour Rules applicable to him i.e. EPF deduction / payment of income tax / GST, workmen compensation etc.
3	Contractor have to deposit the addle. Money as provision in shren एवं अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों को विनियम) अधिनियम 1996 की धारा 18(3) एवं 18(4) एवं 18(3) सह पठित नियम 251 के अनुसार असंगठित क्षेत्र के कर्मकारों के हित के लिए नियोजकों से निर्माण लागत का एक प्रतिशत की दर से उपकर मंडल को देय होगा जो कर्मकारों के हित के लिए विभिन्न कल्याणकारी योजनाओं में राशि का उपयोग किया जाना है।


Superintending Engineer
 (City Circle-1) C.S.P.D.C.L., Raipur

अनुसूची-“ख”
अनुसूचित नियोजन भाग-एक के 45 नियोजन

(दिनांक 01.04.2019 से 30.09.2019 तक)

(दिनांक 01.10.2019 से 31.03.2020 तक)

क्र.	श्रेणियों का वर्ग	गोन का नाम	न्यूनतम मूल वेतन		परिवर्तनीयत महगार्द भत्ता		कुल वेतन रुपये में		गोन का नाम	न्यूनतम मूल वेतन		परिवर्तनीयत महगार्द भत्ता		कुल वेतन रुपये में	
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन		प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन
1	अनुसूचित	अ	8320.00	320.00	600.00	23.08	8920.00	343.08 (343)	अ	8320.00	320.00	800.00	30.77	9120.00	350.77 (351)
		ब	8060.00	310.00	600.00	23.08	8660.00	333.08 (333)	ब	8060.00	310.00	800.00	30.77	8860.00	340.77 (341)
		स	7800.00	300.00	600.00	23.08	8400.00	323.08 (323)	स	7800.00	300.00	800.00	30.77	8600.00	330.77 (331)
2	अनुसूचित	अ	8970.00	345.00	600.00	23.08	9570.00	368.08 (368)	अ	8970.00	345.00	800.00	30.77	9770.00	375.77 (376)
		ब	8710.00	335.00	600.00	23.08	9310.00	358.08 (358)	ब	8710.00	335.00	800.00	30.77	9510.00	365.77 (366)
		स	8450.00	325.00	600.00	23.08	9050.00	348.08 (348)	स	8450.00	325.00	800.00	30.77	9250.00	355.77 (356)
3	अनुसूचित	अ	9750.00	375.00	600.00	23.08	10350.00	398.08 (398)	अ	9750.00	375.00	800.00	30.77	10550.00	405.77 (406)
		ब	9490.00	365.00	600.00	23.08	10090.00	388.08 (388)	ब	9490.00	365.00	800.00	30.77	10290.00	395.77 (396)
		स	9230.00	355.00	600.00	23.08	9830.00	378.08 (378)	स	9230.00	355.00	800.00	30.77	10030.00	385.77 (386)
4	अनुसूचित	अ	10530.00	405.00	600.00	23.08	11130.00	428.08 (428)	अ	10530.00	405.00	800.00	30.77	11330.00	435.77 (436)
		ब	10270.00	395.00	600.00	23.08	10870.00	418.08 (418)	ब	10270.00	395.00	800.00	30.77	11070.00	425.77 (426)
		स	10010.00	385.00	600.00	23.08	10610.00	408.08 (408)	स	10010.00	385.00	800.00	30.77	10810.00	415.77 (416)

टीप : न्यूनतम वेतन अधिनियम, 1948 के अन्तर्गत 45 अनुसूचित नियोजनों की सूची परिशिष्ट-“अ” तथा इस संबंध में स्पष्टीकरण परिशिष्ट-“ब” में देखें।

(सुतोय कुमार सिंह)
श्रमायुक्त एवं सहाय प्राधिकारी
न्यूनतम वेतन अधिनियम, 1948
छत्तीसगढ़, रायपुर

Superintending Engineer
(City Circle-1) C.S.P.D.C.L., Raipur