

Job wise labour rates for maintenance works for the year 2018-19- Justification thereof.

S. No.	Particulars	Rate as per SOR for 2017-18	Wages fixed by Collector for Unskilled / Semi-skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2018-19 (Rs.)
1	3 Straitening of leaned poles:-	4	5	6	7	8	9	10	11	12
	(a) Straitening of 140 Kg 8 mtr long PCC poles (Including pit digging Straitening & back filling with boulders & ramming including cost of boulders)	326	325	3	2	35.50	244	279	56	335
	(b) Straitening of 272 Kg 9.1 mtr long PCC poles (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	474	325	4	2	80	325	405	81	486
1	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	590	325	5	2	97.50	406	504	101	605
	(d) R.S.Joist (125x70 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	491	325	4	2	94.50	325	420	84	503
	Dismantling of damaged old support completely (For 33 KV & 11 KV lines)									
	(a) 140 Kg 8 mtr long PCC pole Taking out of V cross arm, top clamp insulators, 4 pin cross arm etc. de-erection of pole & shifting	273	325	2	2	70	163	233	47	279
2	(b) 272 Kg 9.1 Mtr long PCC Pole Taking out of V cross arm, top clamp insulators etc., de-erection of pole & shifting	298	325	2	2	90.50	163	253	51	304
	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) Cutting of pole by gas cutter / Dismantling, taking out of V-cross arm, top clamp insulators etc. shifting & loading in Board's vehicle.	838	325	5	2	304.50	406	711	142	853
	(d) R.S.Joist (125x70 mm) Cutting of pole by gas cutter / Dismantling, taking out of cross arm, 4 pin cross arm and insulators etc. shifting and loading in company's Vehicle	744	325	4	2	305	325	630	126	756
3	Renovation of stay providing stay wire only where stay rod is found intact	147	325	2	1.50	4	122	126	25	151
	New stay- Pit digging, grouting, concreting & erection									
	(i) New stay for 33 KV line 20 mm	481	350	4	2	60.50	350	411	82	493
4	(ii) New stay for 11 KV line 16 mm	229	350	1	2	105.50	88	193	39	232
	(a) For urban areas with concreting cement will be provided by the board	240	380	1	2	107.50	95	203	41	243
	(b) For rural areas with stone block	209	380	1	2	81.50	95	177	35	212
	Painting of poles : cleaning of metallic surface by wire brush, 2 coats of red oxide & 1 coat of Aluminium paint on all the steel surfaces, paint will be provided by the board & wire brush will be provided by the contractor.									
5	(a) Rail pole, R.S.Joist, H-Beam	234	380	1	2	102.50	95	198	40	237
	(b) V-cross arm & Top clamp 11 KV & 33 KV	171	380	2	1.50	3.50	143	146	29	175
	(c) LT 3 / 4 / 5 Pin cross arm each	63	380	1	1	6.50	48	54	11	65
	(d) DC channel (8'.5'.4', SPC) for 33 KV & 11 KV	130	380	2	1	16	95	111	22	133

W

24	LT jumper renovation	31	325	1	0.65	0	26	26	5	32
	Tree cutting and trimming of tree branches :-									
25	a. LT line	90	350	1	1.77	0	77	77	15	93
	b. 11 KV Line	102	350	1	2	0	88	88	18	105
	c. 33 KV Line	173	350	2	1.50	17	131	148	30	178
	Replacement of Distribution box	395	350	2	2	159	175	334	67	401
	Replacement of cable (3.5 core) Replacement will be with lugs materials will be provided by the Company									
26	a. 300 sq. mm.	605	350	4	2	164	350	514	103	617
	b. 150 sq. mm.	542	350	4	2	112	350	462	92	554
	c. 70 sq. mm.	414	350	3	2	90	263	353	71	423
	Replacement of DO fuse unit (each)									
27	a. 33 KV	165	325	2	1.50	19	122	141	28	169
	b. 11 KV	109	325	2	1	12	81	93	19	112
28	Replacement of phase main switch	220	325	2	2	25.50	163	188	38	226
29	Replacement of porcelain kit-kat	71	325	1	1.50	0	61	61	12	73
	Replacement of lightning arrestor as per schedule									
30	a. 33 KV	128	325	1	2	28	81	109	22	131
	b. 11 KV	60	325	1	1.27	0	52	52	10	62
31	Replacement of Silica Jel	32	325	1	0.68	0	28	28	6	33
32	Renovations of Jumpers of DT S/s. alongwith lugging (material will be supply by the Company)	293	325	2	2	87	163	250	50	299
33	Commissioning of meter at DT (installation of meter box, meter, cabling, commissioning complete by skilled labour)	843	325	5	2	309	406	715	143	858
	proposed Additional Job work already incorporated in 2017-18									
1	Shifting of location of meter from inside to outside consumer premises labour charges									
	a. Single phase connection	226	325	2	2	31	163	194	39	232
	b. Three phase connection	357	325	3	2	61	244	305	61	366
2	Replacement of old meter box by installation of new pillar Box in complex including fixing & laying of cables and shifting of connection only labour charges	4547	325	10	8	639	3250	3889	778	4667
3	Indexing of consumer premises, survey, meter card fixing, writing of S/C no., line diagram preparation, from DT to consumer premises each DT wise	35	325	1	0.74	0	30	30	6	36
4	DT meter installation including CT / meter box and meter installation (only labour charges)	780	325	4	2	335	325	660	132	792
5	Laying of HT ABC cable (labour charges) 33 kV	8541	325	15	12	30	7313	7343	1469	8811
6	Laying of HT ABC cable (labour charges) 11 kV	5882	325	15	8	177	4875	5052	1010	6062
7	Fixing of LT junction box on the pole for providing LT connection	189	325	2	2	0	163	163	33	195
8	Providing Earthing of Distribution S/s including pit digging laying and connecting wire to support, X-mer etc. Back filling of pit by Black Cotton soil (only labour charges) per pitwise	780	325	4	2	335	325	660	132	792
	proposed Additional Job work already incorporated in proposal 2017-18									
1	Cleaning of 33/11 KV S/s. Yard (approx. 75% area of S/s.) including removal of grasses, tree plants removal dusting etc.	3849.60	325	12	6	373	2925	3298	660	3958
2	Renovation of yard levelling and metalling with cleaning, scraning labour charges	2400.00	325	8	6	110	1950	2060	412	2472
	ABC cable end joint replacement and fixing		325							
3	a. Per phase	805	325	4	2	355.50	325	681	136	817
	b. Straight joint	1289	325	6	4	129	975	1104	221	1325
	c. LT end joint per phase	101	325	1	2	5	81	86	17	104
	d. LT straight joint per phase	134	325	1	2	32.50	81	114	23	137

MA

कार्यालय सहायक श्रमायुक्त रायपुर, जिला-रायपुर

(डॉ० माहुरकर गली, कचहरी चौक, रायपुर)

E-Mail ID – Raipuralc1@gmail.com, Ph 0771-2223953

परिपत्र

रायपुर, दिनांक ११ / ११ / 2017

श्रमायुक्त कार्यालय छत्तीसगढ़, रायपुर की अधिसूचना क्रमांक/आठ/न्यूवे०/श्र०आ० 2017/7536, दिनांक 23.09.2017 के अनुसार जनवरी 2017 से जून 2017 तक की अवधि में अखिल भारतीय उपभोक्ता मूल्य सूचकांक का औसत 276.33 जबकि पूर्व छमाही औसत 277.5 था (2001=100 जनवरी 2016 से जनवरी 2018 के आधार आकड़े) इस प्रकार वर्तमान सूचकांक में कोई वृद्धि नहीं हुई है। परिणामतः 45 अनुसूची नियोजन में 01.04.2017 से प्रभावशील परिवर्तनशील महंगाई भत्ता यथावत दिनांक 01.10.2017 से 31.03.2018 तक देय है। अनुसूची "ख" एवं अनुसूची "ग"

अनुसूची- "ख"

अनुसूचित नियोजन भाग-एक के 45 नियोजन हेतु मासिक दैनिक वेतन की दरें, जिसमें परिवर्तनशील महंगाई भत्ता सम्मिलित है।)

दिनांक 01.10.2017 से 31.03.2018 तक

(आंकड़े रूपयों में)

क्र.	श्रमिकों का वर्ग	जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महंगाई भत्ता		कुल वेतन	
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन
1	अकुशल	अ	8320.00	320.00	130.00	5.00	8450.00	325.00
		ब	8060.00	310.00	130.00	5.00	8190.00	315.00
		स	7800.00	300.00	130.00	5.00	7930.00	305.00
2	अर्द्धकुशल	अ	8970.00	345.00	130.00	5.00	9100.00	350.00
		ब	8710.00	335.00	130.00	5.00	8840.00	340.00
		स	8450.00	325.00	130.00	5.00	8580.00	330.00
3	कुशल	अ	9750.00	375.00	130.00	5.00	9880.00	380.00
		ब	9490.00	365.00	130.00	5.00	9620.00	370.00
		स	9230.00	355.00	130.00	5.00	9360.00	360.00
4	उच्च कुशल	अ	10530.00	405.00	130.00	5.00	10660.00	410.00
		ब	10270.00	395.00	130.00	5.00	10400.00	400.00
		स	10010.00	385.00	130.00	5.00	10140.00	390.00

1/2/1

अनुसूची-“ग”

विभिन्न शासकीय विभागों में कार्यरत दैनिक वेतन भोगी श्रमिकों एवं कर्मचारियों के मासिक एवं दैनिक वेतन तथा परिवर्तनशील महंगाई भत्ता भी शामिल है।
दिनांक 01.10.2017 से 31.03.2018 तक (आंकड़े रूपयों में)

क्र.	श्रमिकों का वर्ग	जोन का नाम	न्यूनतम मूल वेतन		परिवर्तनशील महंगाई भत्ता		कुल वेतन	
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन
1	अकुशल	अ	8320.00	277.33	130.00	4.33	8450.00	281.67
		ब	8060.00	268.67	130.00	4.33	8190.00	273.00
		स	7800.00	260.00	130.00	4.33	7930.00	264.33
2	अर्द्ध कुशल	अ	8970.00	299.00	130.00	4.33	9100.00	303.33
		ब	8710.00	290.33	130.00	4.33	8840.00	294.67
		स	8450.00	281.67	130.00	4.33	8580.00	286.00
3	कुशल	अ	9750.00	325.00	130.00	4.33	9880.00	329.33
		ब	9490.00	316.33	130.00	4.33	9620.00	320.67
		स	9230.00	307.67	130.00	4.33	9360.00	312.00
4	उच्च कुशल	अ	10530.00	351.00	130.00	4.33	10660.00	355.33
		ब	10270.00	342.33	130.00	4.33	10400.00	346.67
		स	10010.00	333.67	130.00	4.33	10140.00	338.00

टीप :- जोन का विवरण

1. जोन "अ" के अंतर्गत सम्मिलित क्षेत्र :-

- नगर पालिक निगम रायपुर, दुर्ग, भिलाई-चरोदा एवं बीरगांव सीमा के भीतर एवं नगर पालिक निगम सीमा से 16 कि.मी. तक का क्षेत्र।
- राज्य के समस्त औद्योगिक क्षेत्र एवं औद्योगिक विकास केन्द्र।
- नया रायपुर विकास प्राधिकरण क्षेत्र।
- प्रदेश में स्थित ऐसे समस्त कारखाने जिनके कारखाना अधिनियम, 1948 के तहत 300 या उससे अधिक श्रमिकों के लिए अनुज्ञापति ली गयी है।

- जोन "ब" :- नगर पालिक निगम राजनांदगांव, बिलासपुर, कोरबा, रायगढ़, अबिकापुर, जगदलपुर, चिरमिरी, एवं धमतरी नगर पालिक निगम सीमा के भीतर एवं नगर निगम सीमा से 8 कि.मी. तक का क्षेत्र।
- जोन "स" :- जोन "अ" एवं "ब" में सम्मिलित क्षेत्र को छोड़कर।
- घोषित न्यूनतम वेतन दरों से कम वेतन का भुगतान नियोजित कर्मचारियों/श्रमिकों को न करें अन्यथा विधान के उल्लंघनार्थ कार्यवाही की जावेगी।
- अनुसूची "ग" के लिए उपरोक्त निर्धारित वेतन दरें 30 से विभाजित करने से सप्ताहिक विश्राम दिवस का पारिश्रमिक सम्मिलित नहीं है।

सहायक श्रम आयुक्त
रायपुर जिला - रायपुर
रायपुर, दिनांक 8/11/2017

पू.क./एफ/दस/रा.जि./2017/ 7026-7030
प्रतिलिपि :-

- श्रमायुक्त, छ.ग. शासन नया रायपुर की ओर सादर सूचनार्थ।
- कलेक्टर, रायपुर, जिला-रायपुर की ओर सादर सूचनार्थ।
- अधीक्षक यंत्री, जल संसाधन विभाग/लोक निर्माण विभाग/लोक स्वास्थ्य यांत्रिकी विभाग।
- सर्वे जिला अधिकारी की ओर सूचनार्थ।
- नियोजक/श्री

सहायक श्रम आयुक्त
रायपुर जिला - रायपुर